(Autonomous) (ISO/IEC - 27001 - 2013 Certified)

#### WINTER-17 EXAMINATION

17503 **Subject Name: Public Health Engineering Model Answer** Subject Code:

### **Important Instructions to examiners:**

- 1) The answers should be examined by key words and not as word-to-word as given in the model answer scheme.
- 2) The model answer and the answer written by candidate may vary but the examiner may try to assess the understanding level of the candidate.
- 3) The language errors such as grammatical, spelling errors should not be given more Importance (Not applicable for subject English and Communication Skills.
- 4) While assessing figures, examiner may give credit for principal components indicated in the figure. The figures drawn by candidate and model answer may vary. The examiner may give credit for any equivalent figure drawn.
- 5) Credits may be given step wise for numerical problems. In some cases, the assumed constant values may vary and there may be some difference in the candidate's answers and model answer.
- 6) In case of some questions credit may be given by judgement on part of examiner of relevant answer based on candidate's understanding.
- 7) For programming language papers, credit may be given to any other program based on equivalent concept.

Q.	Sub	Answer	Marking
No.	Q.N.		Scheme
L.	(A)	Attempt any <u>THREE</u> of the following	12Mark
	(a)	State any four types of demand of water. State the four factor affecting rate of demand.	
	Ans.	Following are the demands of water.	
			(02
		1) Domestic demand.	Marks)
		2) Public and industrial demand.	Any fou
		3) Losses and wastages.	1/2
		4) Fire demand.	Marks
		5) Commercial and Institutional demand.	each
		Following are the factors affecting rate of demand.	
		i) Size of city	
		ii) Habits of people	
		iii) Climatic conditions	(02
		iv) Cost of water	Marks)
		v) Commerce and industry	Any fou
		vi) Quality of water	1/2
		vii) Efficiency of water supply system	Marks
		viii) System of sanitation.	each
		ix) System of supply	
		x) Metering of supply	



1.	(b)	State desirable limit as per IS for	thr following parameters of drinking water	
(A)	Ans.	Following are the desirable limit a	·	
		Characteristics	Desirable	(04
		(i) Color	10	Marks)
		(ii) Turbidity	5 NTU	1/2
		(iii) Total dissolve	J.	Marks
		(iv)Total hardnes		each
		(v) Chlorides	250 mg/lit	
		(vi) Iron (Fe)	0.3 mg/lit	
		(vii) pH	6.5 to 8.5	
		(viii) Fluorides	0.6 to 1.2 mg/lit	
		<ol> <li>Plain chlorination.</li> <li>Pre Chlorination.</li> <li>Post Chlorination.</li> <li>Double Chlorination.</li> <li>Break point chlorination.</li> <li>Super Chlorination.</li> <li>Dechlorination.</li> </ol>		marks) Any four 1/2 Marks each
			intain in order to take care of all the bacteria which will be because of exposure of water to atmosphere.	(02 marks)
1. (A)	(c) Ans.	State methods of aeration. Explain Following are the methods of ae a) Cascade aerator. b) Spray Nozzles. c) Air diffusion method. d) Trickling bed method. a) Cascade aerator.		(01 mark for Any four Methods)
			Elevation  Plan	(01 mark for Fig.)
		They consist of concrete steps of provided at the edge of each step	ver which water comes down in thin sheet. Weir may b	e <b>(02</b>



(Autonomous) (ISO/IEC - 27001 - 2013 Certified)

	over steps co	omes in contact with the	marks)
ly one method of aei	ration)		
following			06 Marks
	om surface sourc	e and sub surface source	oo marks
			(06
			marks.)
urface of the earth	1.Water that is t	rapped under the earth's	,
ake is known as			
lable in surface	2. Large amount	of water available in sub	
less than sub	surface source.		
			01 mark
sed to evaporation.	3.Sub surface wa	ater is not exposed to	each
	evaporation.		
•	4. Sub surface w	ater mainatain constant	
_	temperature.		
ntain patheogenic		ater free from patheogenic	
ore for surface	6. Treatment cos	st is less.	
Water Treatment m	ethods. Explain a	any one method with neat	
nt Advanced Water T	Fraatmant matha	.de	(02
nt Auvanceu water i	reatment metho	ous.	marks)
			for Any
			four
			Methods
			½ each.
]		Pressure	
		] ] membrane	(02
			marks)
alt		Pure Salt	,
lution		<del>(                                      </del>	
	100		
		Fig. 2	
process deminerali	zation water is	produced by forcing water	
_	•	•	
·	<del>-</del>		
one compartment is i	ca with water t		Ì
sed through the men	nbrane towards t	the compartment containing	(02
_		the compartment containing s of the membrane creates a	(02 marks)
	following I quantity of water from the frace and sub surface ce Water urface of the earth aske is known as illable in surface less than sub sed to evaporation.  emperature gs. Intain patheogenic more for surface I Water Treatment must Advanced Water Treatment must be able membrane (or eable membrane).	following I quantity of water from surface source rface and sub surface source of water ce Water urface of the earth ake is known as  ilable in surface less than sub  surface source.  sed to evaporation.  emperature gs. ntain patheogenic  for surface  I Water Treatment methods. Explain a surface water and the surface water and t	following quantity of water from surface source and sub surface source rface and sub surface source of water.  The water of the earth aske is known as surface is known as Sub Surface water.  The water is not exposed to evaporation.  The water is not evaporation.  The wa




(Autonomous) (ISO/IEC - 27001 - 2013 Certified)

the osmotic pressure of the solution. (Shown in fig 1)

The process can be reversed by applying sufficient pressure to the concentrated solution to overcome the osmotic pressure force the net flow of water through the membrane towards the dilute phase. The solute concentration (impurity) builds up on one side of the membrane while relatively pure water passes through the membrane. In order to obtain adequate solvent (water) flux through the membrane, pressures of the order of 4000 to 7000 kN/m2 are required. (Shown in fig 2)

### **Electrodialysis:**

Electrodialysis uses ion-selective membranes and an electrical potential difference to separate anions and cations in solution.



02 marks

In the past electrodialysis was most often used for purifying brackish water, but it is now finding a role in hazardous waste treatment. Metal salts from plating rinses are sometimes removed in this way.

Fig. shows a simple dialysis cell in which waste water may be deionised. As shown in the figure two types of membranes (anionic and cationic) are arranged alternatively to form many compartments between the electrodes placed at the two ends. When the voltage is applied across the cell containing mineralised water, the anions migrate to the positive electrode and the cations migrate to the negative electrode. This causes solution in alternate compartments to become more concentrated while that in the remaining becomes more dilute. The electric power requirement is proportional to the number of ions removed from the water.

02 marks

In the electrodialysis process, organic molecules are not removed and they can collect on and clog the membranes. Another disadvantage of this method is that it still leaves concentrated waste water to be disposed of by some appropriate scheme. The process does not require any chemical additives and has low energy requirements and as such it can be an economically feasible means of demineralisation.

### Ion exchange:

This technique has been used extensively to remove hardness, and ironand manganese salts in drinking water supplies. It has also been used selectively to remove specific impurities and to recover valuable trace metals like chromium, nickel, copper, lead and cadmium from industrial waste discharges. The process takes advantage of the ability of certain natural and synthetic materials to exchange one of their ions.



(Autonomous) (ISO/IEC - 27001 - 2013 Certified)

A number of naturally occuring minerals have ion exchange properties. Among them 04 marks the notable ones are aluminium silicate minerals, which are called zeolites In the water softening process, the hardness producing elements such as calcium and magnesium are replaced by sodium ions. A cation exchange resin in sodium form is normally used. The water-softening capability of cation exchange can be seen when sodium ion in the resin is exchanged for calcium ion in solution. (no need of diagram) Microstraining: It is a special type of filtration procedure which makes use of filters oven from stainless steel wires with opening only 60-70 µm across to remove very small particles. High flow 04 marks rates and low back pressures are normally achieved. (no need of diagram) NOTE: Students may explain any one advance water treatment method. 2. Attempt any FOUR of the following 16Marks Draw layout of city water supply with rapid sand filter, label the parts and state the work (a) carried out by each part. Ans. Layout of city water supply with rapid sand filter Intake Structure with Screens Areation Sedimentation (02 Coagulant **Pumping station** Unit dosing unit Tank marks) Rapid sand Overhead tank Clear water reservoir **Chlorine Pumping Station** Dosing tank **Filters** Distribution network systems Sr. No. Unit **Function** To draw water from source. Intake structures with Pumping station To remove floating matter. 2 Screens To add oxygen in water. 3 Aeration Unit To remove dissolve gases from (02 water. marks) To add coagulant in water. 4 Coagulants dosing tank for any Sedimentation tank remove suspended 5 eight impurities like silt, clay sand etc. remove very fine colloidal matter which are not 6 Rapid Sand Filter removed by sedimentation. Chlorine dosing tank To add chlorine for disinfection. 8 To store treated water Clear water reservoir **Pumping station** To pump water into overhead 9 tank Overhead tank To store water 10 Distribution network systems To distribute water to consumer 11 2. (b) What is principle behind sedimentation with coagulation? State any two types of



(Autonomous)

(ISO/IEC - 27001 - 2013 Certified)

#### Ans.

### coagulant.

### Principle behind sedimentation with coagulation

Coagulants are chemical, added to water to remove the colloidal particles or impurities of raw water and reduce turbidity of water. Principle of coagulation can be explained by two considerations.

- a) Floc formation
- b) Electrical charges.

(03 Marks)

1½ each

- (a) Floc formation: When a coagulant is added to water and mixed thoroughly and thick gelatinous precipitate 'Floc' is formed. Flocattracts and arrests the colloidal particles and makes them settle down.
- **(b) Electrical charges:** Ions from floc possess positive electric charge. Colloidal particles possess negatively charged ions. The floc thus attracts colloidal particles and makes them settle down.

### **Types of Coagulants:**

Following are the main types of coagulants:

- a) Aluminum sulphate Al2 (SO4)3
- b) Chlorinated coppers.
- c) Ferrous sulphate and lime.
- d) Magnesium carbonate.
- e) Polyelectrolytes.
- f) Sodium aluminate.

## (01

Mark) For any

Two

½ each

## 2. (C) Ans.

## Explain in brief the process of backwashing in rapid sand filter.

## Back washing:

Wath water storage tank

Air compressor
unit, if needed

Water from
coagulation
sedimentation

Water level while filtering

Water level while filtering

Head loss
indicator
sedimentation

Water level while
back washing
back wa

(02 Marks for Fig.)

A separate overhead tank is constructed near the filter house to store the water required for back washing of filter. A pump is installed to lift the sufficient quantity of filtered water to be stores in wash water tank.

#### Operation:

Initially, the valves (1) and (4) are closed and valves (5) and (6) are opened out.

The wash water and compressed air are thus forced upwards from the underdrainage through the gravel and sand beds.

Valve (5) is closed after supplying the required amount of air. The dirty water, resulting from washings, overflows into the wash water troughs and is removed by opening the valve (3) through the inlet chamber into the wash water drain. Now open valve (1) and (4) for some time then close valve (4) and put filter in normal working condition by opening valve (2).

(02 Marks)



2.	(d)	What are valves? Why are they required? Sta	te two types of valves with their suitable	
	Ans.	location.		(01
		The fixtures, which are fixed along the distribu	ition system, are known as valves.	Mark)
		They are provided for the following purposes	:	
		(a) To control the rate of flow of water.		(01
		(b) To release or admit air into the pipeline.		Mark)
		(c) To prevent or detect leakage.		for any
		(d) To meet the demand during emergencies.		two ½
		(e) To make the distribution system more efficient	rient	each
		Air Relief Valve.	actic.	Cucii
		<b>Location:</b> In order to provide an exit for accum	oulated air air valves are provided at summits	(02
		along the pipe lines.	idiated air, air vaives are provided at summits	Marks)
		Sluice valve.		-
				One
		Location:	1450 1- 200 1-1-11'1'	mark
		1) They are generally placed at a distance abou		each
_	1	2) For long straight mains, the sluice valves car		
2.	(e)	Differentiate between one pipe and two pipe	· · · · · · · · · · · · · · · · · · ·	
	Ans.	Difference between One pipe and Two pipe p		
		One Pipe System	Two Pipe System	
		1. Waste from sanitary fittings , bath, sinks,	1. Waste water from W.C. and waste water	(04
		basins etc. carried through single pipe.	from other fitting like bath, sink, basins etc.	Marks)
			carried through separate pipe.	01 mark
		2. Waste water from bath, sinks, basins un-	2. Waste water from bath, sinks, basins can	each any
		necessarily gets polluted.	directly used for irrigation purpose.	four
		3. Easy to install in high rise building.	3. Difficult to install in high rise building.	
		4. Require less space for duct and shaft.	4. Require more space for duct and shaft.	
		5. Increases load on waste water treatment	5. Less load on waste water treatment	
		plant.	plant.	
		6. Economical as less pipes are required.	6. Uneconomical as more pipes are	
		o. Leonomical as less pipes are required.	required.	
2.	/£\	Draw a typical layout for water supply arrang	·	
۷.	(f)	1		
		type of pipe	material, sizes etc.	
	Ans.	°	5 6	
		6	R	
		c K		(02
				Marks)
		3 4 50 604	OOT PATH	
		8	F	
			ROAD	
		AB&FG - COMMUNICATION PIPES	BCDE - SUPPLY PIPE PQ & RS - DISTRIBUTING PIPES	
		GH HH HJ CONSUMERS JL PQ RS PIPES 2. FERRULES 4. STOP COCK 6. SECOND STORAGE TANK	1. MUNICIPAL WATER MAIN 3. MUNICIPAL LIMIT 5. FIRST STORAGE TANK	



		Type of Pipe material  Municipal water main (Cast iron pipe/ Concrete pipe)  Communication pipes (PVC / GI pipe)	Size 125 mm to 250 mm 50 mm to 75 mm	(02 Marks)
		Supply pipe (PVC / GI pipe)	25 mm to 50 mm	For any
		Consumers pipes (PVC / GI /Copper Pipe)	25 mm to 50 mm	four ½ each
		(Students may show the arrangement for different plan and apple)	propriate size of pipes)	each
Q.3	a) Ans	Draw sketch of inspection chamber and give it's necessity. Inspection Chamber:  Pipe channel for access to system Stoping concrete/mortar bed or haunching	Cover and frame  Brick wall  Concrete base	02 marks for fig
		Inspection chamber is provided for inspection, cleaning, reline.	epair and maintenance of sewer	02 marks
Q.3	b) Ans	Draw a labeled sketch of reservoir intake.    Intake		04 marks
Q.3	c) Ans	<ol> <li>List the component parts of a drop manhole and state its not.</li> <li>Working chamber: For inspection and cleaning of se</li> <li>Inspection arm and plug: For cleaning, inspection and sewer and plug is providing restriction.</li> <li>Vertical shaft: For connecting branch sewer to main</li> <li>Rungs (Stairs): For ascending and descending for main</li> <li>Benching: For proper laying of the main sewer in con</li> <li>Manhole cover: For covering manhole drop manhole</li> </ol>	wer. d maintenance of the branch sewer. n. ncrete. e cover is provided.	02 marks for parts 02 marks for necessity



	T		1
Q.3	d)	State measures for prevention of pollution of bores and well waters.	
	Ans	1. We should not wash the cloths near bore and well.	
		2. We should not wash utensils near the well.	04 marks
		3. We should not wash animals near the well.	
		4. Septic tank should be far away from bore and well to protect ground water from	
		pollution.	
Q.3	e)	Describe 'water test' and 'air test' with reference to testing of sewers.	
	Ans	Water test: Each section of the sewer is tested for water tightness preferably between	
		manholes. To prevent change in alignment and disturbance after the pipes have been laid,	
		it is desirable to backfill the pipes up to top, keeping at least 90 cm length of the pipe open	
		at the joints. But in case of shorter pipe lengths of stoneware and RCC pipes, it is not	
		possible. With concrete encasement or concrete cradle, partial covering of pipe is not	02 marks
		necessary.	oz marks
		In the case of the concrete and stoneware pipes with cement mortar joints, the testing	
		shall be done after making joints. It is necessary that the pipelines are filled with water for	
		about a week before commencing the application of pressure to allow for the absorption by	
		the wall of the pipe.	
		The testing of the sewer is done by plugging the upper end with a provision for an air	
		outlet pipe with stopcock. The water is filled through a funnel connected at the lower end	
		provided with a plug. After expelling the air through the air outlet, the stopcock is closed	
		and water level in the funnel is raised to 2 m above the invert at the upper end. Water level	
		is noted after 30 minutes in the funnel and the quantity of water required to restore the	
		original level in the funnel is determined. The pipe line under pressure is then inspected	
		while the funnel is still in position. There should not be any leaks in the pipe or joints except	
		small sweating on the pipe surface which is allowed. Leakage in 30 minutes determined by	
		measuring the replenished water in the funnel should not exceed 15 ml in the smaller	
		diameter and 60 ml in the larger diameter per cm diameter of pipe for 100 m length. Any	
		sewer or part that does not meet the test shall be emptied and repaired or re-laid as per	
		requirements and tested again.	
		Air test: It is done by subjecting the stretch of pipe to an air pressure of 100 mm of water	
		by means of a hand pump. The joints shall be assumed to be water tight. The exact point of	02 marks
		leakage can be detected by applying soap solution to all the joints in the line and looking	
		for the air bubble.	
Q.4	A)a	List the operations carried out during periodical cleaning of drainage system.	
	Ans	1. Use of the flexible sewer rod with manila rope for sewer cleaning.	
		2. The composite flexible rod composed of rope tied together with bamboo strips is	04 marks
		lowered inside the manhole by a person on top, while another person inside the	
		manhole thrusts the same in to the sewer in the direction of flow.	
		3. Flushing of sewers is carried out periodically to clear laterals and sewers laid within	
		sufficient slope for maintaining a velocity so as to remove settled material.	
0.4	A \ b		
Q.4	A)b	Explain general principles of building drainage.	
	Ans	1. The drain should be laid in such a way so as to remove the sewage quickly from the	A £
		building. The drain should be laid at such a slope that self-cleaning velocity is	Any four
		developed in them.	01 mark
		2. All the drainage system should be properly ventilated on the house sides. All the	for each
		inspection chambers should be provided with fresh air inlets.	
		3. All the drains should be laid in such a way so as to ensure their safety in future.	



	1	1 , =1 1			<del></del>				<u> </u>		
				be laid	in such	a way	that in fu	ture e	xtension car	n be done easily if	
		desired		r ninos	aaani	na fran	. hausa a	nd ha	th water cha	uld be discharged	
					-	_				ould be discharged	
		over gully traps and should be connected from the drain.  6. All soil pipes should be carried direct to the manholes without gully traps.									
0.4	۸۱۵	•	tate function of (i) air relief valve, (ii) Non-return valve.								
Q.4	A)c Ans								rios somo ai	r with it which	
	Alis					-	•			of air increases, it	
					_	•				ost essential to	02 marks
										e is used for this	UZ IIIdi KS
			ove the a	ccamai	atea an		ine pipe i	c. / ti	r rener varve	. 13 4364 101 11113	
		1		· Non-r	eturn v	alve all	ow water	to flo	w only in on	e direction and	02 marks
			ent it fro						,	e an ection and	
Q.4	A)d	·						S.			
•	Ans	State norms for maintenance of domestic sanitary units.  1. Sanitary fittings should be laid in such a way so as to remove the sewage quickly									
		<u> </u>	e building				•			<i>σ</i> , ,	Any four
		2. The pipe	e line in tl	he sanit	ary fitti	ings sho	ould be p	roperl	y ventilated	on the house	01 mark
		sides.							for each		
		3. Sanitary	/ fittings s	shall be	leak pro	oof.					
		1	Sanitary fittings joints should be water tight.								
		·	5. Sanitary fittings should be cleaned periodically.								
Q.4	B)a				_	•				f water for small	
			a/colony a	and fore	ecast th	e popu	lation of	area ir	1 2021 by ge	ometrical increase	
	Ans	method.	1001		1071		4004		1001	2004	
		Year	1961	-	1971		1981		1991	2001	
		Population	4,320		5,200		7,120		8,000	9,150	
		Geometric incr	ooso motl	hod:							
		Year		Populat	ion	Increa	oco in	Dor	centage incr	oaco in	
		Teal	'	ropulat	.1011	popu			ulation	ease III	
		1961		4320		рори	idtion	РОР	alation		
		1971		5200		880		880	x 100/4320	= 20.37%	
		1981		7120		1920		_	0 x 100/520		03 marks
		1991		8000		880		_	x 100/7120		
		2001	9	9150		1150		_	0 x 100/800		
		Average per d	ecade			IG		21.0	)%		
			•					•			
		P2011 = P[1 + (	IG/100)]n	1							
		= 9150[1	+ (21/100	))]1							01 mark
		= 11072									01 mark
		P2021 = 9150[1	L + (21/10	00)]2							01 mark
		= 13359									OTHINGER
		The water supp	oly deman								
				= 360	)6930 li	t/day.					



(Autonomous)

(ISO/IEC - 27001 - 2013 Certified)


Q.4	B)a
	Ans

State the reason for suitability of two pipe system over one pipe system. Draw a neat labeled sketch of one pipe system partially ventilated.

Two pipe system: This method provides an ideal solution. All the traps used in this system are fully ventilated. Waste pipes are connected through the gully trap. The soil pipes are connected to the drain.

03 marks

03 marks



One pipe system partially ventilated

### Q.5

## a) Ans

Attempt any FOUR of the following:

Explain the procedure of lying of sewers.

- The boring or trial holes are dug along the proposed sewer line to ascertain the nature of ground.
- From the longitudinal section of the sewer line, the position of manhole are studied and located on the ground.
- The center line of the sewer line should be properly maintains


There are two methods which are employed for this purpose.

In the first method, a line parallel to the sewer line is marked on one side. This is known as an offset method it is usually marked at distance of D which is about one half the trench width plus 600mm .the other side is used to dump the excavated material. The offset line should be drawn on that side of the trench which is not likely to be disturbed during the process of excavation of the trench. The temporary bench mark at the intervals of about 200m to 300m should be established along the offset line by carrying the levels from the permanent bench mark. The offset line helps in locating the sewer-line when excavation is carried out to lay sewers.

03 marks

In the second method the two vertical post are driven in to the ground at a distance from the centre line peg.one horizontal rail known as the sight rail is fixed between these posts at a convenient height from the ground level.

(Autonomous) (ISO/IEC - 27001 - 2013 Certified)





		<ul> <li>As the wastewater moves through the film and degraded by a mixed population.</li> <li>The oxygen required for organic degrate the Filter induced by natural draft or verification.</li> <li>As the biological film continues to grow their ability to cling to the medium, a filter. This process is known as sloughing.</li> <li>The sloughed solids are picked up by clarifier for removal from the wasteway.</li> <li>Microorganisms used.</li> <li>The microorganisms used are mainly organic material in the wastewater along with</li> </ul>	radation is supplied by air circulating through entilation.  bw, the microorganisms near the surface lose and a portion of the slime layer falls off the ng. the under-drain system and transported to a ter.  by facultative bacteria that decompose the ch aerobic and anaerobic bacteria. It includes is, and alcaligenes. In the lower reaches of the	02 marks		
Q.5	c) Ans	State role of Maharashtra pollution control board in prevention of pollution.  To plan comprehensive program for the prevention, control or abatement of pollution and secure executions thereof  To collect and disseminate information relating to pollution and the prevention, control or abatement thereof,  To inspect sewage or trade effluent treatment and disposal facilities, and air pollution control systems and to review plans, specification or any other data relating to the treatment plants, disposal systems and air pollution control systems in connection with the consent granted,  Supporting and encouraging the developments in the fields of pollution control, waste recycle reuse, eco-friendly practices etc.  To educate and guide the entrepreneurs in improving environment by suggesting appropriate pollution control technologies and techniques  Creation of public awareness about the clean and healthy environment and				
Q.5	d)	attending the public complaints regard Differentiate between i) Aerobic and Anaerob	01			
	Ans	<ol> <li>i) Aerobic and Anaerobic process</li> <li>Aerobic process</li> <li>1. It occurs in majority of organisms.</li> <li>2. Oxygen is used</li> <li>3. It always releases CO2.</li> <li>4. It generated water.</li> <li>5. It releases entire energy available in glucose as it is fully oxidized</li> <li>6. Aerobic respiration involves five principal steps: glycolysis, pyruvate oxidation, TCA cycle, ETS and chemiosmotic ATP synthesis.</li> <li>7. It yields inorganic end products</li> </ol>	Anaerobic process  1. It occurs in a few organisms (e.g. yeast, and some bacteria and parasitic worms).  2. Oxygen is not used.  3. It may or may not release CO2  4. It does not produce water  5. It releases only 5% of energy available in glucose as it (glucose) is not fully oxidized.  6. It includes just two steps: glycolysis and incomplete breakdown of pyruvate.  7. In yields organic end product with or without inorganic ones.	02 marks (01 mark for one point)		



	8. Aerobic reparation takes place in cytoplasm and mitochondria.  8. Anaerobic respiration takes place cytoplasm only	
0.5	B.O.D. C.O.D.  1. Is the oxygen required for the biochemical oxidation of the decomposable matter at specified temperature within the specified time.  The slandered time and temperature are 5 days 200 C.  B.O.D. C.O.D.  It is the measure of amount of carbon in organic matter  The standard time for this test is 5 hour	02 marks (01 mark for one point)
Q.5 e) Ans	Plot boundary  Man hole B  Inspection chamber (I.C.)  Orawing room  Man hole (M.H.) A with interecepting trap  With interecepting trap  Road  External public sewer line  Man hole  Man hole  Man hole  Stoleware pipe 1 in 60  Gully  Irap  (G.T.)  Kitchen +  Dining hall 9  External public sewer line  Man hole  Road	04 marks




Q.5	f)	Draw flow diagram of activated sludge process plant and explain its working.				
	Ans	Flow sheet of an activated sludge system				
		← Primary treatment — Secondary treatment — >				
		Raw waste    Screens   Grit   Studge   Return sludge   Pump   Excess sludge   Grying   Sludge   Grying   Sludge   Sludge   Grying   Sludge   Sludge   Grying   Sludge   Grying   Sludge   Grying   Sludge   Grying   Sludge   Grying   Grying	02marks			
		<ol> <li>Working:-         <ol> <li>The raw sewage is given the primary treatment in the primary settling tank. The detention period is kept short 1-1.5 hours. The primary settling tank removes less percentage of settable solids. Due to less removal of solids the filter media des not clog.</li> <li>After primary treatment the raw sewage is mixed up with the required quantity of activated sludge which is called return sludge and sent in the aeration tank. The mixer is called as mixed liquor.</li> <li>In the aeration unit the mixed liquor is aerated and simultaneously agitated for 4-10 hr. depending on the degree of purification desired and the strength of the sewage.</li> <li>The aerated mixed liquid is sent in the final settling tank.</li> <li>The effluent from the final settling tank which is clear is disposed of.</li> <li>A part of settled sludge is sent back in the aeration unit for seeding the raw sewage and the excessive quantity is treated and disposed off.</li> </ol> </li> </ol>	02 marks			
Q.6	a)	Write any two reasons for necessity of pre-treatment before trickling filter process in view				
	Ans	of activated sludge process.  1. The main object of primary object of primary treatment process is to remove suspended matters, oils, sand and grit and floating matters etc.  2. In the primary treatment process the sewage is passed through screens, grit chambers, detritus tank and sedimentation tank.  3. The primary settling tank remove less percentage of settable sand due to less removal of solids the filter media does not clog.	04 marks (Any two 02 marks For 01 point)			
Q.6	b)	Explain with neat sketch working of oxidation pond.				
	Ans					



(Autonomous)

(ISO/IEC - 27001 - 2013 Certified)





		Chalking tool.  Socket-or beli-end lead Hemp yarn Spigot end  Spigot and Socket-Joint.	02 marks
Q.6	d) Ans	Give importance of (i) Non-scouring velocity, (ii) Self cleansing velocity.  i) Non-scoring velocity. The interior surface of the sewer pipe gets scored due to the continuous abrasion caused by suspended solids present in sewage. The scoring is pronounced at higher velocity than what can be tolerated by the pipe materials. This wear and tear of the sewer pipes will reduce the life span of the pipe and their carrying capacity. In order to avoid this, it is necessary to limit the maximum velocity that will be produced in sewer pipe at any time. This limiting or non- scouring velocity mainly depends upon the material of sewer.  i) Self-cleaning velocity. The velocity that would not permit the solids to settle down and even scour the deposited particles of a given size is called as self-cleansing velocity. This minimum velocity should at least develop once in a day so as not to allow any deposition in the sewers. Otherwise, if such deposition takes place, it will obstruct free flow causing further deposition and finally leading to the complete blocking of the sewers	02 marks
Q.6	e) Ans	List any four types of pipes used for conveyance of water and state the advantage of cost iron pipes.  a) cast iron pipe b) wrought iron pipe c) Steel pip d) Concrete pipe e) Cement line cast iron pipe f) Asbestos cement pipe g) Copper and lead pipe h) Wooden pipe i) Vitrified clay pipe. Advantage of cost iron pipes:-  Cast iron pipe is the preferred choice for handling high pressures and loads of water.  Cast iron pipe have long life.	Any four ½ mark for each